

Resources required

Machine	<ul style="list-style-type: none"> • Purpose built masthead piling rig and ancillary equipment to rig the machine for work activities
Area	<ul style="list-style-type: none"> • Facilities for rig travel and parking • Certificated piling platform for piling works to take place • Area clear of hazards e.g. overhead and underground services and with a designated exclusion zone
Other equipment	<ul style="list-style-type: none"> • Piling and ancillary equipment to meet the pile specification • Fully qualified rig operator and additional supporting labour (including reporting line) • Resources and materials to ensure the installation of piles • Equipment to remove spoil at the piling location (if required) • Pile layout drawing and pile schedule/design • Permit to dig • Lifting equipment for lifting operations (if required) • Applicable lifting accessories for all loads (if required) • Items to create restrictions for manoeuvring (cones, barriers and signage).
Pile specification	<ul style="list-style-type: none"> • Minimum of 20 linear metres*
Notes	<ul style="list-style-type: none"> • The machine selected for the test must be in serviceable condition and conform with current legislation • The piling rig operator must be certificated and competent • All lifting accessories must be fit for purpose and certificated • The weight of all loads/ancillary equipment must be known • Specification detailing position, sequence, type and depth of completed piles • All certification, permits to dig and lift plans (where required) must be authorised and current <p>*Linear metres are defined by the length and number of piles e.g. 2 x 10 metre piles or 5 x 4 metre piles etc.</p>

Activity instructions

Sequence	<ul style="list-style-type: none"> Due to the nature of the equipment, piling activities can be undertaken on different rigs, locations and different days if required. CPCS must be informed prior to any tests taking place and be given full details of any divided tests <p>The test must be completed collectively within a given time. The specifications' section gives further information</p>
Preparing for work	<ol style="list-style-type: none"> Carry out pre-use checks to all ancillary equipment required for the construction of piles Establish communication methods with the rig operator Ensure, by communication with the operator, that the rig/mast is prepared for travel
Travelling and manoeuvring <i>(refer to activity measurements)</i>	<ol style="list-style-type: none"> Guide the rig to the work area by providing directions to the rig operator Guide the rig through a restriction whilst travelling to the work area
Setting up for work	<ol style="list-style-type: none"> Prepare the rig/mast and ancillary equipment for defined piling works Ensure resources and materials are correct, available and of sufficient quantity etc.
Working task <i>(refer to activity measurements)</i>	<ol style="list-style-type: none"> Locate the rig onto the pile position within specified tolerances Ensure the pile is plumb/at the correct angle throughout the piling activity Ensure the pile is installed to specification Control the working area and maintain the exclusion zone
Completing work	<ol style="list-style-type: none"> On completion of the placing of each pile, confirm the pile has been constructed to specification Instruct the rig operator to configure the rig for travel and guide the rig to the next working position
Shutting down	<ol style="list-style-type: none"> On completion of all activities, instruct the rig operator to configure the rig for travel and guide the rig to a safe parking area on firm level ground Provide specified assistance to the operator for shut-down and securing procedures
Notes	<ul style="list-style-type: none"> The test may be carried out during actual work and discrepancies allowed for compared to the stated activities and pile types including time needed to move to a new pile position Checks unable to be carried out may be assessed by the Tester using verbal questions For item 15, instructions for assistance must be defined before shut-down and securing activities begin

Activity measurements

Manoeuvring restrictions	<ul style="list-style-type: none">• Maximum of the width of the rig plus 800mm
Pile placing	<ul style="list-style-type: none">• Within 75mm of the given positions (or specified tolerances if less than 75mm)
Pile measurement	<ul style="list-style-type: none">• Pile complete within vertical tolerance of the specification
Completed pile(s)	<ul style="list-style-type: none">• At least 20 linear metres
Test timings	<ul style="list-style-type: none">• The test must be completed within a total accumulated time 3 hours

THIS PAGE HAS BEEN LEFT BLANK INTENTIONALLY

Basic details

Test ref:	Candidate name:
Tester ref:	Candidate ref:
Tester ref:	Date of test:
Make and model:	Start time of test:
	Duration:

Mandatory

	Correctly carried out during the test?	Y/N
Preparing	1. All pre-use checks to equipment (or responses to relevant questions)	
Travelling	2. Assist in setting the rig correctly for travel	
	3. Guide the rig through restrictions	
	4. Maintain a position of safety during travelling activities	
	5. Encountered hazards identified and cleared	
Setting up	6. Exclusion area checked and safe prior to setting up for piling works	
	7. Rig positioned accurately for piling works (reference rods etc.)	
	8. Ensuring rig was level for piling works	
	9. Confirm pile details are correct with operator	
Working	10. Communication arrangements confirmed with the rig operator	
	11. Aligned the mast for the required pile angle	
	12. Ensure that the exclusion zone is maintained throughout	
	13. Spoil removed to the agreed area (if applicable)	
	14. Form pile to the specification (drawing/schedule)	
	15. Confirm weight of all loads with rig operator	
	16. Rig stability maintained (checked platform condition)	
	17. Pile constructed in accordance with industry and company standards	
Shutdown	18. Rig re-configured from piling to travelling duties	
	19. Parked securely in appropriate place	
Other	20. All shut down and securing procedures	
	21. Legislation, manufacturers' and health and safety requirements complied with	
	22. Test completed within given time	

All of these items must be awarded

Achieved / Not achieved

Faults

Candidate incorrectly carried out the following:

		Fault	Mark	Penalty
	1. Signal code confirmed with operator		3	
	2. All around observation before rig is moved (no obstructions)		2	
	3. All around observation whilst rig is travelling		2	
Working	4. All around observation made before/during slewing		2	
	5. Ensure all ancillary equipment is checked for travel		3	
	6. Minimal manoeuvring maintained during piling work		1	
	7. Follow planned sequence of operation		2	
	8. Materials organised and ready for use		3	
	9. Remain in a position of safety during piling operation		3	
	10. Maintain communication with rig operator		2	
Not exceeded eight penalties		Total penalties		
Achieved / Not achieved				